



ITNOA Apartment FAIZABAD ROAD



Company Profile

Max Infra Ventures Pvt. Ltd. is a well-recognized name in Lucknow's real estate business, started its operations in late 2017. It has grown exponentially setting benchmark for quality standard innovating in style and technology that captured the attention of its judicious customers. Max Infra Ventures is not only delivering quality projects and but also providing a better quality of life and environment to its customers.

Company's motto is simple -

"Excellent customer care with highest customer satisfaction."



Company's vision is to make the world a better place to live in, to transform and uplift the quality of living and life style of each and every individual and to contribute significantly into the development of real estate....!

Level up your live! Invest with Max Infra Ventures!

Specifications



Structure designed for the highest Seismic considerations for zone as stipulated by the code and better safety.

Foundation:

Reinforced concrete footings and column with raft.

Living/ Dining Room & All Bedrooms

Flooring/skirting: Good Quality / Vitrified Tiles of Rang Wall Finishes: Acrylic Emulsion on POP punning

Ceiling: Oil Bound Distemper

Toilets

Flooring: Ceramic Tiles

Wall Finishes : Ceramic Wall Tiles up to Dado level (approximately 2100 mm). Oil Bound Distemper.

Ceiling Finishes: Oil Bound Distemper

Sanitary ware: Good Quality

Kitchen

Flooring/Skirting: Vitrified Tiles/Ceramic Tiles/Marble

Stone

Wall Finishes: Oil Bound Distemper on the walls

Ceiling: Oil Bound Distemper on plaster provision for

installation of geysers.

Counter: Granite top with sink.

External Wall Finishes

External Wall

Finishes: External grade anti fungal/anti algal paint

from

reputed makes and brands

Staircase

Flooring: Polished Indian Stone/Indian Marble / Granite on treads, risers and landings: Railing: Painted M.S. handrails and Dalustrades Wall Finishes: Oil Bound Distemper on plaster

Common Passage

Flooring: Vitrified Tile.

Wall Finishes: White Wash/ Oil Bound Distemper on

plaster.

Ceiling Finisher: White Wash/ Oil Bound Distemper on

plaster.

Doors and Windows

Main Entrance Door: Painted hardwood frame door

with flush door.

Internal Doors: Painted/Polished Flush Door with Door

Skin.

Hardware: Locks, Handles and knobs.

Windows and External Glazing : powder coated

Aluminium frame/Frame windows with clean glass.

Electrical Wiring and Installations

Fixtures and Fittings : IS compliant switches/sockets, distribution

boxes and circuit breakers from standard makes and brands.

Wiring : IS compliant copper wiring in concealed conduits.

Adequate provision for light points.

Plumbing with standard : ISI compliant CPVC water supply pipes with standards walves & accessories. ISI compliant PVC waste pipes & trops.

Note: visual representations shown in this brouchre are purely conceptual, Building plans, Specifications, Layout plans Etc are tentative & subject to variation & modification by the company or the competent authorities sactioning plans.





UNIT - 1, 2, 3, 4, 5 & 6




Covered Area - 655.28 sq.ft. Super Area - 830 Sq.ft.

UNIT - 7, 8 & 9



Covered Area - 487.10 sq.ft. Super Area - 570 Sq.ft.



TYPICAL FLOOR PLAN



Ventures Pvt. Ltd.

⊕ www.maxinfraventures.com | ⊙ info@maxinfraventures.com